

## NOTES

P-01 New steel frame stair core with steel stairs including a new lift shaft.

**P-02** New external escape stair shared with apartment building to be constructed Allow provisional sum for temporary solution during construction. Constructed in steel with solid treads (infill stone/concrete).

P-03 New cast iron ramp at Castle street with glazed inserts.

P-04 Basement areas at Castle street opened up & and new cast iron pavement lights with glazed inserts added to the areas.

**P-05** Refurbish drinking fountain.

**P-06** New Leinster granite paving and kerbing. Existing gullies relocated out on road. No alterations to main drainage line.

P-07 Curved granite stone steps to Cork Hill cleaned and repointed.

**P-08** New Leinster granite stone steps and landing to top of Castle street steps to provide part M compliant entrance.

P-09 Cast iron pavement light with glazed insert.

P-10 Castle Street entrance door to be retained rehung to open out.

P-11 Shared exit gate. Escape via push pad/emergency button for Newcomen, Castle Gate & Carnegie Centre.

P-12 Timber flooring to be retained and cleaned. Floor boards to be lifted to insert services and insulation and relaid. Floor strengthened on the upper floors.
 P-13 Three new granite steps to match existing.

P-14 Refurbish portland hanging stairs. - clean and repoint with graft repairs replacements throughout.

P-15 Refurbish granite hanging stairs. - clean, repoint and repair where required.
 P-16 Stone floor to be retained, cleaned and repointed.

**P-17** New masonry wall/infill. Infill in brick with lime plaster.

P-18 New internal timber stud partition.

**P-19** New sanitaryware and fitout in newly configured WCs new wall and floor tile throughout.

P-20 New fire-rated timber door to match the existing historic doors.

**P-21** Existing doors to be upgraded to 30 minute fire rated door systems. See door schedule and photographic survey for details.

P-22 New non-fire-rated timber door.

**P-23** Timber window to be retained & repaired, windows generally in good working order, minor repairs may be required. See window schedule and photographic survey for details, including upgrades.

P-24 New fire-rated timber door.

**P-25** New slim profile glazed metal fire screen and door to be placed within original archway/opening, or between existing walls.

P-26 Plaster all external walls (except under street vaults & corridor) with 30 to 40mm diathonite insulated lime plaster.

**P-27** Clean, repair and re-point 50% of remaining dividing walls and allow for application of lime plaster.

P-28 New insulated limecrete slab.

 $\mbox{P-29}$  Allow for clean down and repointing of the retaining walls in the vaults of 50% of the surface area.

**P-30** Clear out all existing insulation wool from attic spaces to facilitate inspection and repair of ceilings. Install new breathable insulation at ceiling level (e.g. sheep wool or wood fibre boards).

P-31 New cast iron rainwater goods and SVPs. See elevations for details.

**P-32** Allow for overhauling and rehanging iron panelled door in basement leading to the area.

**P-33** Walls around existing fabric to be squared off in stud and plasterboard (around wall between 0-06 & 0-07).

**P-34** New accessible WC facility in the existing cast in-situ concrete safe. Safe door to be retained and refurbished.

**P-35** Existing chimneypieces to be carefully cleaned, chimney flues to be inspected and cleaned. See chimney piece photographic survey.

**P-36** Newly inserted historic style chimneypiece and cast iron grate.

**P-37** New cast iron grate to be installed into existing chimneypiece.

**P-38** New external door, fire rated if required. See elevation drawings.

**P-39** Retain existing furniture piece.

P-40 New Part M, contemporary style fitout incorporating a tea station.

P-41 New contemporary style furniture fitouts.

P-42 New service risers. Plaster cornices to be retained to front of riser.

**P-43** New stairs with timber treads between second and third floor. A portion of the existing stairs retained on site for display.

**P-44** Retain all existing timbers carrying out repairs to existing only where required. New spliced in timbers of matching timber species to be repair approach.

P-45 New timber window. See window schedule for details.

P-46 Addition of new 60 minute door on push pad operation to the doorway between stair 1 and stair 2. Door to be automatically locked in event of a fire.
P-47 New janitor's sink.

GENERAL NOTES - All drawings to be read in conjuncture with method statement, photographic survey and schedules submitted along with the drawings. - All works on site will be completed on site in accordance to the method statement submitted along with the planning application.				
Project Newcomen Bank Building 16 Castle Street, Dublin 2 Client Dublin City Council	Howley Hayes Cooney <sup>19</sup> Rock Hill, Blackrock, Dublin, A94 D235 ol 278 4644			
Drawing	01 278 4644			

Proposed Second Floor Plan			hhcarchitecture.ie		
Project Stage	Date	<sup>Scale</sup>	Project No.	Drawing No.	Revision
Planning	16.02.2024	1:100@A3	0569	L-203	-