THIS DRAWING IS FOR INFORMATION PURPOSES ONLY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PRODUCING WORKING DRAWINGS

Church of Annunciation Development
Results - Horizontal Illuminance (lux)
Eav= 5.91
Emin= 1.45
Emax= 14.56
Emin/Emax= 0.10
Emin/Eav= 0.25
Emax/Eav= 2.46

Apartment Courtyard/Square
Results - Horizontal Illuminance (lux)
Eav= 5.08
Emin= 1.73
Emax= 10.68
Emin/Emax= 0.16
Emin/Eav= 0.34
Emax/Eav= 2.10

Car Parking Area
Results - Horizontal Illuminance (lux)
Eav= 8.70
Emin= 3.08
Emax= 15.01
Emin/Emax= 0.21
Emin/Eav= 0.35
Emax/Eav= 1.73

Luminaire Data
Luminaire A FLEXIA TOP 5304 Deep shape PC 20 LH351C@300mA NW 740 230V
Lamp 20 LH351C@300mA NW 740 230V MF 0.84
Luminaire B AXIA 2.1 5167 Integrated lenses 16 OSLON SQUARE GIANT@760mA
Lamp 16 OSLON SQUARE GIANT@760mA NW 740 230V 00-36-648 MF 0.84
Luminaire C AXIA 2.1 5167 Integrated lenses 16 OSLON SQUARE GIANT@400mA
Lamp 16 OSLON SQUARE GIANT@400mA NW 740 230V 00-36-648 MF 0.84

Key
- Luminaire A Column
- Luminaire B Column
- Luminaire C Column
- ○ Beam Aiming Target
- □ Photometric Centre

All Dimensions in metres

REV	DESCRIPTION	DRN	CKD	DATE
P01	PART 8 SUBMISSION	GD	SF	07.03.2024

ISSUE: PLANNING STAGE

semple mckillop
NATURALLY INNOVATIVE **CONSULTING ENGINEERS**
ISO 9001 ISO 14001 ISO 45001 Registered
Belfast +44 (0)28 90331700
Castleblayney +353 (0)42 9749570
www.semplemckillop.com admin@semplemckillop.com

PROJECT TITLE
NDFA SOCIAL HOUSING BUNDLE 4

DRAWING TITLE
DEVELOPMENT AT CHURCH OF THE ANNUNCIATION, FINGLAS, CO. DUBLIN
ILLUMININANCE PLOT

DRAWING REFERENCE	DRN	SCALE
SHB4-CAF-DR-SMK-ME-P3-6000	DMcD	A1 1:250

Project - Originator - Volume - Level - Type - Role - Number