SHB4&5 Church of Annunciation - Outline Planting Schedule - Rev: P02

TREE PLANTING

NB: All trees should be full and well-shaped, bark unmarked and have healthy root systems. All trees to have a 2m clear stem unless otherwise specified.

SPECIES	ABBREVATION	FORM	GIRTH/SPEC	NO.
Acer griseum	Ag	Rootballed	Min. 3 breaks from base, min. 2.5m high, WR	1
Acer saccharinum	As	Rootballed	Advanced heavy standard, 16-18cm girth, min. 4m high, 3xtr	1
Amelanchier lamarckii	Al	Multistem	Min. 3 breaks from base, min 1.5m high	4
Betula utilis jacquemontii	Bu 'J'	Rootballed	Select standard, 10-12cm girth, min. 3m high, 3xtr	3
Cornus kousa 'China girl'	Ck 'Cg'	Multistem	Min. 3 breaks from base, min. 3m high	2
Heptacodium miconoides	Hm	Multistem	Min. 3 breaks from base, min 1.5m high	3
Magnolia kobus	Mk	Multistem	Min. 3 breaks from base, min. 2.5m high, WR	1
Malus sylvestris	Ms	Rootballed	Select standard, 10-12cm girth, min. 3m high, 3xtr	3
Malus sylvestris	Ms	Multistem	Min. 3 breaks from base, min 1.5m high	4
Prunus padus	Pp	Rootballed	Select standard, 10-12cm girth, min. 3m high, 3xtr	4
Sorbus aucuparia 'Sheerwater Seedling'	Sa 'Ss'	Rootballed	Extra heavy standard, 14-16cm girth, min. 3m high, 3xtr	6
Tilia x europaea	Ta	Rootballed	Extra heavy standard, 14-16cm girth, min. 3m high, 3xtr	1

SHRUB PLANTING MIXES

NB: Plants planted in 450mm free draining topsoil and all planted areas dressed with 50mm fine grade bark mulch.

SPECIES	SPEC	COMMENTS
MIX 1 - To building curtilage		
Prunus lusitanica	min. 10L pot	min. 1.25-1.50m high
Crocus tommasinianus	top size bulbs	
MIX 2 - Boundary hedge mix		
Crataegus monogyna (75%)	min. 10L pot	min. 1m high
Corylus avellana (10%)	min. 5L pot	
Viburnum opulus (10%)	min. 5L pot	
Prunus spinosa (2.5 %)	min. 2L pot	
Rosa canina (2.5%)	min. 2L pot	
Crocus tommasinianus	top size bulbs	
Amelanchier lamarckii	min. 1.2m high	multistem, accent plant
MIX 3 - Shady planting mix		
Dryopteris filix-mas	min. 3L pot	
Helleborus foetidus	min. 5L pot	
Polygonatum multiflorum	min. 10L pot	
Saxifraga stolonifera	min. 2L pot	
Crocus tommasinianus	top size bulbs	

PLANTING

Existing Trees for retention
Refer to arboricultural drawings and survey

Proposed Tree
Refer to planting schedule for species and spec

Grass
Amenity Grass seeding on min. 150mm approved topsoil

Grass (meadow)
Amenity Grass seeding - maintenained as meadow

Reinforced grass
Loksand stabiliser, seeded with amenity grass mix and maintained as meadow

Shrub mix 1
Refer to planting schedule

Shrub mix 2
Refer to planting schedule

Shady planting mix
Refer to planting schedule

REV	DESCRIPTION	DATE
01	Multistems/shady mix added	10.06.24

Mitchell + Associates

PROJECT TITLE:
Social Housing Bundle 4

CLIENT:
Dublin City Council

DRAWING NAME:
CAF Outline Planting Plan

DRAWING NUMBER:
0005

JOB NUMBER:
LSOC003

DRAWN BY	CHECKED	DATE
Andres Echeverry	FP	10.06.2024
STATUS: PLANNING	**SCALE:** 1:200 @ A1	**REVISION** 01

NOTES:
All dimensions are in millimeters unless otherwise stated and shall be checked and confirmed by the contractor on site. Any discrepancies shall be immediately reported to the landscape architects. Work to figured dimensions only - Do not scale from drawing. Do Not Scale. Use Figured Dimensions Only. Not for Construction Purposes unless Specifically Marked.

© THIS DRAWING IS COPYRIGHT OF MITCHELL + ASSOCIATES