

clear stem to 1.8 m high minimum

upright development, strong single leader
bark free of damage free of abrasion and disease

species specific root development

Due to settlement, all trees should be re-tendioned after planting.
Soil must be compacted properly for Deadman system to work effectively
Topsoil (sandy loam to BS3882) backfilled into Stratacells and into tree pit

species specific root development fitting to age and size of the appropriate tree

NATIVE WOODLAND MICROFOREST PLANTING


sufficient fibrous roots

rootball fitting to the species and size of the plant

consistent rooting

planting.
Soil must be compacted properly for Deadman system to work effectively
Topsoil (sandy loam to
BS3882) backfilled into
Stratacells and into tree pit.
Soil to be laid in layers of
150mm thick and gently hand tampered to minimise settlement.
If possible delay installation of gravel surface dressing for 2 weeks after topsoil installation.
Top-up soil level prior to installation after settlement.

202



Mitchell + Associates

PROJECT TITLE:

Social Housing Bundle 4&5
CLIENT:
NDFA

DRAWING NAME:
Typical planting details
DRAWING NUMBER:
SHB5-BMD-DR-MAL-L-P1-0202
JOB NUMBER:
LSOC003
STATUS:

DRAWN:

Planning

SCALE: 1:25 @ A1

NOTES:
All dimensions are in millimeters unless otherwise stated and shall be checked and confirmed by the contractor on site. Any discrepancies shall be immediately reported to the landscape architects. Work to figured dimensions only - Do not scale from drawing. Do Not Scale. Use Figured Dimensions Only. Not for Construction Purpose unless Specifically Marked. © This Drawing is Copyright of Mitchell + Associates.

mitchell.ie info@mitchell.ie