ISO A1 594mm x 841mm
Approved: EF
Last saved by: CRAIG.SWEENEY(2021-06-22) Last Plotted: 2021-07-01
Filename: \\NA.AECOMNET.COM\LFS\EMEA\DUBLIN-IE\DBL1\LEGACY\IEDBL1FP001\IEDBL1FP001-V1\PCC\DPE\TECH\TECH\AECOM-PROJECTS\2017\DCC BALLYMUN PLAZA\04CAD\4.1SHEET\PLOT ANNOTATION\60556950-SHT-20-000-L-0003.DWG Checked:RL
Printed on 100% Post-Consumer Recycled Content Paper

Shrub Mix A (SM-A)

Species	Designation	Root Type	Height mm	Spread mm	Total plants / sq.m	% Mix in Area
Sarcococca confusa	Container Grown	3 Litre Pot	600-900	300-500	5	10%
Pittosporum	Container Grown	2 Litre Pot	200-400	300-400	5	10%
Hebe "Great Orme"	Container Grown	5 Litre Pot	700-900	300-500	3	20%
Erysinum "Bawles mauve"	Container Grown	5 Litre Pot	900-1200	400-500	4	10%
Calamagrostis "Karl foerster	Container Grown	3 Litre Pot	400-600	200-300	3	30%
Nepeta "Six hills giant"	Container Grown	3 Litre Pot	100-200	300	4	20%

		sq.m
General Notes:	Total Area :	141
	(does not take gradients into account)	

Shrub Mix B (SM-B)

Species	Designation	Root Type	Height mm	Spread mm	Total plants / sq.m	% Mix in Area
Ilex crenata	Container Grown, Bushy, 5 breaks	15 Litre Pot	800 - 1000		4	10%
Hebe "Great Orme"	Container Grown, Bushy, 3 breaks	2 Litre Pot	200 - 300	200 - 300	2	10%
Astelia chathamica	Container Grown	2 Litre Pot	200 - 300	200 - 300	5	25%
Convolvulus cneorum	Container Grown	2 Litre Pot	200 - 300	200 - 300	8	10%
Polystichum setiferum	Container Grown	3 Litre Pot	200 - 300	200 - 300	5	25%
Sarcococca confusa	Container Grown, Bushy, 6 breaks	3 Litre Pot	200 - 300	200 - 300	2	20%

		sq.m
General Notes:	Total Area :	666
	(does not take gradients into account)	

Shrub Mix C (SM-C)

Species	Designation	Root Type	Height mm	Spread mm	Total plants / sq.m	% Mix in Area
Stipa arundinacaea	Container Grown	2 Litre Pot	200 - 300		4	20%
Dryopteris sp.	Container Grown	2 Litre Pot	200 - 300	200 - 300	4	30%
Geranium macrorrhizum	Container Grown	2 Litre Pot	200 - 300	200 - 300	5	20%
Heuchera	Container Grown	2 Litre Pot	200 - 300	200 - 300	5	30%

		sq.m
General Notes:	Total Area :	17
	(does not take gradients into account)	

Tree Planting	Form	Age / Condition	Girth	Clear Stem	Height	Roots	Comments
SEMI MATURE							
Prunus avium	Std	3 x transplanted	20 - 25 cm	2.5m	min. 350cm	Rootball	Well formed crown
Platanus acerifloa	Std	3 x transplanted	20 - 25 cm	2.5m	min. 350cm	Rootball	Well formed crown
Betula utilis var. "Jaqcuemontii"	Multi stem	4 x transplanted			min. 450cm	Rootball	Multi stem, 3 stems
Acer griseum	Std	3 x transplanted	18 - 20 cm	1.75m	min. 350cm	Rootball	Well formed crown

Bulb Planting (BM1)

	Planting Method	% Mix
Camassia, Muscari, Allium, Narcissus sp.	Hand Sown	100%

General Notes: Total Area for Bulb Mix is 140 sq.m.
(does not take gradients into account)

Amenity Lawn Mix (G1)

	Planting Method	% Mix
Amienity Grass Mix	Hand Sown	100%

N

0 12.5 25 m
1:500

AECOM

PROJECT
BALLYMUN PLAZA

CLIENT
DUBLIN CITY COUNCIL

CONSULTANT
AECOM Ireland Limited
4th Floor Adelphi Plaza
St Georges Street, Dun Laoghaire
01 238 3100 tel
www.aecom.com

REGISTRATION

ISSUE/REVISION

I/R	DATE	DESCRIPTION
B	23/06/2021	ISSUE FOR PLANNING
A	29/01/2021	ISSUE FOR PLANNING

PROJECT NUMBER
60556950

SHEET TITLE
Ballymun Plaza
Site Plan

SHEET NUMBER
60556950-SHT-20-000-L-0003